

VT OFFICE:

P.O. Box 766 • 527 Hinesburg Rd.
Richmond, VT 05477
802-434-3499
800-759-3237
FAX 866-308-8372



NH OFFICE:

Claremont Center Prof. Bldg.
425 Washington Street, Suite 108
Claremont, NH 03743
603-543-9505
866-350-5438
FAX 866-308-8372

QUOTATION

Savaria vertical platform lift to be installed at the Madrid Library, Madrid, NY:

Savaria V1504-144 vertical platform lift (12' max. lifting height), *standard beige color, 36" x 55.75" custom size platform to fit existing hoistway*, two stops, in-line openings, 750 lb. capacity, 20 FPM speed, call stations on each landing, emergency stop and alarm on platform control, emergency light on platform, emergency battery lowering, 11/2 hr. fire-rated *factory painted automatic* swing landing entrance door assemblies with Prolock elevator interlock & concealed hinges (2), 2:1 chain-hydraulic drive system, and grab rail.


Equipment: \$22238.00
Labor: 2000.00
Total Installed Price: \$24238.00

DEDUCT: \$1500 for standard factory primed door assemblies. Finish painting by others.

DEDUCT: \$400 for standard 36" x 54" platform size.

ADD: \$1500 for optional lift color.

- Shaftway doors, frames, and hardware are to be supplied and installed by Accessibility Systems. Framed rough openings are to be provided by others, to accept the new door assemblies. Drywall work after door assemblies are installed, is to be provided by others.
- Blocking in wall behind lift tower (above CMU wall) is to be provided by others.
- Provide temporary support at top of shaftway to attach hoist, to lift tower into shaftway.
- Crating material is to be disposed of at a suitable location on-site, provided by others.
- Customer is to provide a 120 volt 20 amp grounded dedicated circuit with fused lockable disconnect (with auxiliary contact), installed by a licensed electrician.
- This quote may be withdrawn after thirty (30) days.

Authorized signature:  9/10/17
Robert B. Weber, Pres.

